
16770



Call Us First! DO NOT RETURN TO STORE.

For immediate help with assembly or product information call our toll-free number:

1-888-827-9056

or email:

customerservice@backyardproductsllc.com

Our staff is ready to provide assistance.

April through October M - F 8:00 AM to 7:00 PM EST

Saturday 8:30 AM to 4:30 PM EST

November through March M - F 8:00 AM to 5:00 PM EST



16770 06

06/16/2011

GABLE 10' x 8' (305 x 244)


ASSEMBLY MANUAL

BUILDING	SIZE	

ACTUAL FLOOR SIZE

BASE MODEL	10' x 8' (305 x 244 cm)	10' x 7' 8-5/8" (305 x 235,3 cm)
ADD ONE 10' x 4'	10' x 12' (305 x 365,8 cm)	10' x 11' 8-5/8" (305 x 357,2 cm)
ADD TWO 10' x 4'	10' x 16' (305 x 487,7 cm)	10' x 15' 8-5/8" (305 x 479 cm)

KEEP THIS MANUAL FOR FUTURE REFERENCE



⚠ IMPORTANT! ⚠READ INSTRUCTIONS THOROUGHLY PRIOR TO BEGINNING ASSEMBLY.

BEFORE YOU BEGIN

• BUILDING RESTRICTIONS AND APPROVALS

Be sure to check with local building department and homeowners association for specific restrictions and/ or requirements before building.

ENGINEERED DRAWINGS

Contact our Customer Service Team if engineered drawings are needed to pull local permits.

SURFACE PREPARATION

To ensure proper assembly you must build your shed on a level surface. Recommended methods and materials to level your shed are listed on page 10.

· CHECK ALL PARTS

Inventory all parts listed on pages 3 - 5. Contact our Customer Service Team if any parts are missing or damaged.

· ADDITIONAL MATERIALS

You will need additional materials to complete your shed. See page 6 for required and optional materials and quantities.




- CUSTOMER SERVICE -



Call: 1-888-827-9056 email: customerservice@backyardproductsllc.com


TOOLS



Safety! Always use approved safety glasses during assembly.

HELPFUL REMINDER SYMBOLS


Look for these symbols for helpful reminders throughout this manual.



ORIENT LUMBER AND TRIM FOR BEST APPEARANCE


Framing lumber is graded for structural strength and not appearance. Exterior trim is graded for one good side.

Always install the material leaving the best edge and best surface visible. Please remember that these blemishes in no way negatively affect the strength or integrity of our product. (See Fig. $\bf A$, $\bf B$, $\bf C$.)



PARTS IDENTIFICATION AND SIZES

	Part identi	ification is on some parts.	WOOD SIZE CONVERSION CHART Nominal Board Size Actual Size
			2" x 4"1-1/2" x 3-1/2" (3,8 x 8,9 cm) 1" x 4"3/4" x 3-1/2" (1,9 x 8,9 cm)
	RS	RS	2" x 3"1-1/2" x 2-1/2" (3,8 x 6,3 cm)
		tions for part stamp.	1" x 3"3/4" x 2-1/2" (3,8 x 6,3 cm)
1	10x8'	GABLE 10' X 8' INVENTORY YOUR PAR	
		We suggest sorting parts by the	
	x1	LT 2 x 3 x 22-1/8" (5 x 7,6 x 56 cm)	
		NH 2 x 3 x 46-1/4" ((5 x 7,6 x 117,5 cm)
	x6	OV	2 x 3 x 69" (5 x 7,6 x 175,3 cm)
77	x4	OY	2 x 3 x 72" (5 x 7,6 x 183 cm)
WALL	x4	РВ	2 x 3 x 77" (5 x 7,6 x 196 cm)
	x2	PM	2 x 3 x 92-5/8 " (5 x 7,6 x 235,3 cm)
	x2	PR	2 x 3 x 94-1/2" (5 x 7,6 x 240 cm)
	□ x4	7/16 x 2-1/2 x 24-3/4" (1,1 x 6,3 x	62,9 cm)
S			
ER	x6	6 x 24" (15 x 61 cm)	
E	x6	CV	2 x 4 x 65-7/8" (5 x 10 x 167 cm)
RAFTERS			
	x4	CD 2 x 3 x 54-5	/16" (5 x 7,6 x 138 cm)
	☐ x2	HS	1 x 3 x 94-3/4"(2,5 x 7,6 x 240,1 cm)
TRIM	x5		A GAUGE BLOCK FOR 3/4" (19 mm) MEASUREMENT
T R			3/4" (19 mm)
	x4	GBZ 1 x 3 x 8-1/2" (2,5 x 7,6 x 21,6 cm)	RIGHT PAINTED RED
	x4	3/4 x 6-1/4 x 11-7/8" (1,9 x 15,8 x 30 cm)	LEFT PAINTED GREEN
	ı		
R	☐ x2	00	2 x 3 x 69" (5 x 7,6 x 175,3 cm) <i>Finger Jointed</i>
DOOR			
Ď	x1	ZJ	5/8 x 3 x 72" (1,6 x 7,6 x 183 cm)



DAL)TC	IDEN	TIEIC	ATIO	M AA	חו	SIZES
	1/2	IUEN			N AN		

		ntification is I on some parts.	WOOD SIZE CONVERSION CHART Nominal Board Size Actual Size 2" x 4"1-1/2" x 3-1/2" (3,8 x 8,9 cm) 1" x 4"3/4" x 3-1/2" (1,9 x 8,9 cm)
	RS	RS	2" x 3"1-1/2" x 2-1/2" (3,8 x 6,3 cm)
		ations for part stamp.	1" x 3"3/4" x 2-1/2" (3,8 x 6,3 cm)
	10x4'	GABLE 10' X 4' EXTENTING INVENTORY YOUR PAINWEST SORTING PARTS by the suggest sorting parts by the sugg	RTS before you begin.
	x2	NK 2 x 3 x 48" (5 x	7,6 x 122 cm)
WALL	x4	OV	2 x 3 x 69" (5 x 7,6 x 175,3 cm)
<u>\</u>	x2	7/16 x 2-1/2 x	48" (1,1 x 6,3 x 122 cm)
	x2	3/8 x 5 x 48" (0	0,9 x 12,7 x 122 cm)
RAFTERS	x4 x4	6 x 24" (15 x 61 cm)	2 x 4 x 65-7/8" (5 x 10 x 167 cm)
TRIM	x2	FO 1 x 3 x 48	" (2,5 x 7,6 x 122 cm)
WALL PANELS	x2	3/8 x 48 x 72" (1 x 122 x 183 c	m)
OOF PANELS	x2 x2	7/16 x 19" x 48" (1,1 x 48 x 122 cm 7/16 x 47-7/8" x 48" (1,1 x 121,6 x	

Roof panels are 7/16" (11 mm) thick.

ADDITIONAL MATERIALS


FOUNDATION OR FLOOR MATERIALS

- This shed kit does not include a wood floor frame. It does not include any floor panels.
- See page 8 for the additional floor panel sizes and quantities required.
- This shed does not include any leveling materials.
- See the FLOOR LEVELING section on page 10 for recommended methods and suggested materials to properly level your floor, as this will vary depending on your specific site.

COMPLETING YOUR SHED
You will need these additional materials:
10x8' 10x12' 10x16' ALL SIZES
3-TAB SHINGLES (Bundles)
OPTIONAL MATERIALS
DRIP EDGE (Feet)
REFER TO THE BACK OF THIS MANUAL AND THE MANUFACTURER'S INSTRUCTIONS FOR INSTALLATION OF SHINGLES, DRIP EDGE AND FELT.
NOTES

CONCRETE FOUNDATION

If you choose to install your kit on a concrete slab refer to the diagram below. Attach the sill plates on the foundation as shown, and continue on to page 9.



Allow new concrete slabs to cure for at least seven (7) days.

• A treated 2 x 4" (5 x 10 cm) sill plate is required when installing your shed on concrete.


Purchase full length treated lumber, or butt shorter pieces end-to-end and seal seams with caulk.

- Use a high quality exterior grade caulk beneath all sill plates.
- Fasten 2 x 4" (5 x 10 cm) sill plates to slab using approved concrete anchors (fasteners not included).
- Check local code for concrete foundation requirements.

WOOD FLOOR FRAME (Not Included)

If you choose to build a wooden floor system, you will need treated 2 x 4" boards cut to size and nails. Floor panel sizes and quantities are shown below.





INSTRUCTION MANUAL LAYOUT

TABS ARE DISPLAYED AT THE OUTSIDE EGDE OF INSTRUCTION PAGES TO IDENTIFY MODEL SIZE.



Use tabs to make sure you are following the correct instructions.

GABLE 10' X

GABLE 10' x 8':

Look for this tab throughout instructions.



If tab is not displayed, skip to next page including 10' x 8' tab

GABLE 10' x ∞

GABLE 10' x

12

GABLE

10' x 16'

10' x

GABLE

GABLE 10' x 12':

Look for this tab throughout instructions.



If tab is not displayed, skip to next page including 10' x 12' tab

10' x GABLE

GABLE 10' x 16':

Look for this tab throughout instructions.



If tab is not displayed, skip to next page including 10' x 16' tab

/Î\ IF ALL TABS ARE DISPLAYED, FOLLOW ALL INSTRUCTIONS /Î\ REGARDLESS OF MODEL SIZE.



/!\ NOTE: GABLE 10' x 8' image shown standard on pages applicable to all sizes.




OPTIONAL WOOD FRAME FLOOR LEVELING OPTIONS

There are multiple ways to level your floor frame. Our recommended leveling method is shown below.

Leveling materials are not included in this kit.

PREFERRED METHOD - 4x4 TREATED RUNNERS (Typical for 10' x 8' Kit)



PLOOR FRAME NOT INCLUDED

MATERIAL REQUIRED

10' x 8' x2	4" x 4" x 10' (10 x 10 x 305 cm) Treated Lumber
10' x 12' x3	$4" \times 4" \times 12'$ (10 x 10 x 365,8 cm) Treated Lumber
10' x 16' x3	4" x 4" x 16' (10 x 10 x 487,7 cm) Treated Lumber

Fasteners for Frame to 4"x 4".


(3" Screws shown as one option.) Minimum 3" screws / exterior grade.

x24	3"	(7,6 cm
x48	3"	(7,6 cm

x60 ----------------------- 3" (7.6 cm

① Use only wood treated for ground contact and fasteners approved for use with treated wood.





LEVELING METHODS

- Level under 4x4 runners only.
- Locate leveling material 12" from ends of runners and no more than 48" apart.
- Asphalt shingles should be used between 4x4 runners and blocks or treated lumber. Never use shingles in direct contact with ground.
- For best results and aiding in water drainage use gravel under each concrete block.

LEVELING MATERIALS

Gravel
Solid Masonry Blocks in 1", 2", 4" or 8" thickness
2x4 Treated Lumber
Asphalt Shingles
Land Carlos Mark and the set 400 and an account of

/ Leveling higher than 16" not recommended.

LEVELING & SQUARING A 10 x 8' FLOOR FRAME (Not Included)



- FOR 10' x 12', SKIP TO PAGE 12
- FOR 10' x 16', SKIP TO PAGE 13.



$\langle ! angle$ LEVEL AND SQUARE FLOOR FRAME



Before attaching floor decking, it is important to level and square the floor frame. A level and square floor frame is required to correctly construct your shed.




VBEGIN

- 2 Use level and check the frame is level before applying floor panels.
- Check for frame squareness by measuring diagonally across corners. If the measurements are the same, the frame is square. The diagonal measurement will be approximately 151-1/2" (385 cm).
- When the frame is level and square, secure one side of frame to 4x4 runners using one fastener at ends of each runner. At the opposite end of the frame, secure the frame to 4x4 runners with one fastener at ends of each runner making sure the frame remains square (Fig. A).

FINISH

Once the floor frame is level and square fasten the frame at each point the frame contacts the 4x4 runners (Fig. B). Go to page 14.



LEVELING & SQUARING A 10 x 12' FLOOR FRAME (Not Included)



LEVEL AND SQUARE FLOOR FRAME




Before attaching floor decking, it is important to level and square the floor frame. A level and square floor frame is required to correctly construct your shed.



VBEGIN

FINISH

- 2 Use level and check the frame is level before applying floor panels.
- Check for frame squareness by measuring diagonally across corners. If the measurements are the same, the frame is square. The diagonal measurement will be approximately **184-7/8**" **(469,5 cm)**.
- When the frame is level and square secure one side of frame to the 4x4 runners using one fastener at ends of each runner. At the opposite end of the frame, secure the frame to 4x4 runners with one fastener at ends of each runner making sure the frame remains square (Fig. A).
- Once the floor frame is level and square fasten the frame at each point the frame contacts the 4x4 runners (Fig. B). Go to page 14.



/

LEVEL AND SQUARE FLOOR FRAME



Before attaching floor decking, it is important to level and square the floor frame. A level and square floor frame is required to correctly construct your shed.




VBEGIN

- 2 Use level and check the frame is level before applying floor panels.
- 3 Check for frame squareness by measuring diagonally across corners. If the measurements are the same, the frame is square. The diagonal measurement will be approximately 223-1/2" (567,7 cm).
- When the frame is level and square secure one side of frame to the 4x4 runners using one fastener at ends of each runner. At the opposite end of the frame, secure the frame to 4x4 runners with one fastener at ends of each runner making sure the frame remains square (Fig. A).

FINISH

Once the floor frame is level and square fasten the frame at each point the frame contacts the 4x4 runners (Fig. B). Go to page 14.






NOTE: GABLE 10' x 8' shown standard throughout manual



Check the floor frame is level after installing floor panels. Re-level if needed.






• The floor should used as a stable work surface for wall construction.

HINT:

 Organize your assembly procedure during the build process to avoid over-handling of the walls.




RAFTER ASSEMBLY JIG

PARTS REQUIRED:

x2 GAA 3/4 x 3 x 5" (1,9 x 7,6 x 12,7 cm)

x2 GBZ 3/4 x 3 x 8-1/2" (1,9 x 7,6 x 21,6 cm)








- Build a **Jig** to ensure all **Rafters** are assembled the same.
- Mark a straight line on the **Floor** from corner to corner (**Fig. A**) or on sill plates to fit measurements (**Fig. B**).
- 3 Screw blocks in place to measurement shown.





Make sure blocks are square and at 125" (317,5 cm)


н You have finished building a **Rafter Jig**.




NOTE: 10'x8' Gable Floor Shown








NOTE: 10'x8' Model Shown




- 3 Orient parts on edge on floor as shown.
- 4 Use two 3" screws at middle connection.


FINISH
5 You have finished building your back wall frame.





BACK WALL PANELS x29 **PARTS REQUIRED: x1 3/4" GAUGE BLOCK**








Nail using 2" nails 6" apart on edges and 12" apart inside panel.



Do not nail in groove.










GABLE 10' x 8'


GABLE 10' x 12'


GABLE 10' x 16'











10' x 8' SIDE WALL FRAMES

x28 ⊨

PARTS REQUIRED:

7/16 x 2-1/2 x 24-3/4" (1,1 x 6,4 x 62,9 cm)

2 x 3 x 69" (5 x 7,6 x 175 cm)

x2 PM 2 x 3 x 92-5/8" (5 x 7,6 x 235,3 cm)




3" (7,6 cm)



- FOR 10' x 12', SKIP TO PAGE 31.
- FOR 10' x 16', SKIP TO PAGE 35.

BEGIN

- Orient parts on edge on floor. Measure and mark from end of boards.
- Use two 3" nails at each mark.




10' x 8' SIDE WALL FRAME - SOFFIT

PARTS REQUIRED:


x2

3/8 x 5 x 93-1/4" (0,9 x 12,7 x 236,9 cm)




- 3 Place panel onto 2 x 3 with primed side against 2 x 3 (Fig A)
 - Neep panel flush along entire edge of 2 x 3 top plate (Fig A).
- Attach soffit panel flush to 2 x 3 (Fig A) and with 3/8" offset at ends (Fig. B, C) using eleven 1-1/4" screws.






10' x 8' SIDE WALL PANELS

PARTS REQUIRED:





x58



GABLE 10' x 8




Ensure your wall frame is square by installing one panel and squaring frame.

Place the 48 x 72" panel onto wall frame with primed side up as shown. Note the lip and square edges.

Use the gauge block to mark the 3/4" measurement on the wall stud. Locate the panel flush under the soffit panel. Secure panel with two 2" nails in the corners (Fig. A).

Move to the opposite end. Using the long edge of the panel as a lever move the panel side-to-side until you have a 3/4" measurement on the wall stud. Secure corner with two 2" nails.



29

10' x 8' SIDE WALL PANELS

PARTS REQUIRED:







3/8" x 48" x 72" (1 x 122 x 183 cm)







8

Place **48"** panel on frame as shown with primed side facing up. **NOTE THE SQUARE AND LIP EDGES.**


Nail using 2" nails 6" apart on edges and 12" apart inside panel.







Carefully flip your sidewall over. Repeat **STEPS 1-8** to assemble your second side wall.







You have finished building both of your side walls. Go to page 39.


10' x 12' SIDE WALL FRAMES

√BEGIN

- Orient parts on edge on floor. Measure and mark from end of boards.
- 2 Use two 3" nails at each mark.

IMPORTANT! You will build two walls the same.






10' x 12' SIDE WALL FRAME - SOFFIT

PARTS REQUIRED: x2 3/8 x 5 x 48" (0,9 x 12,7 x 122 cm) x2 3/8 x 5 x 93-1/4" (0,9 x 12,7 x 236,9 cm)

- Place panels onto 2 x 3 with primed side against 2 x 3 as shown (Fig A)
 - Keep panel flush along entire edge of 2 x 3 top plate (Fig A).
- Attach soffit panels flush to 2 x 3 (Fig A) and with 3/8" offset at ends (Fig. B, C) using (16) 1-1/4" screws.





10' x 12' SIDE WALL PANELS



Ensure your wall frame is square by installing one panel and squaring frame.


(1 x 122 x 183 cm)

Place the 48 x 72" panel onto wall frame with primed side up as shown. Note the lip and square edges.

Use the gauge block to mark the 3/4" measurement on the wall stud. Locate the panel flush under the soffit panel. Secure panel with two 2" nails in the corners (**Fig. A**).

- Move to the opposite end. Using the long edge of the panel as a lever move the panel side-to-side until you have a 3/4" measurement on the wall stud. Secure corner with two 2" nails.
- Nail the panel using 2" nails 6" apart on edges and 12" apart inside panel.

 Do not nail in groove.



10' x 12' SIDE WALL PANELS **PARTS REQUIRED:** x148 2" (5 cm) 3/8" x 48" x 72" **x4** (1 x 122 x 183 cm) Place 48" panels on frame as shown with primed side facing up. NOTE THE SQUARE AND LIP EDGES. Do not nail Nail using 2" nails 6" apart on edges and 12" apart inside panel. To draw panels tight at seams angle nail. Flush 12" (30 cm) 6" (15 cm) 48" (122 cm) SQUARE EDGE **SQUARE** EDGE Carefully flip your sidewall over. Repeat STEPS 1-8 to assemble your second side wall.



You have finished building both of your side walls. Go to page 39.

10' x 16' SIDE WALL FRAMES

PARTS REQUIRED: x4 7/16 x 2-1/2 x 48" (1,1 x 6,4 x 122 cm) x14 OV 2 x 3 x 69" (5 x 7,6 x 175 cm) x2 NK 2 x 3 x 92-5/8" (5 x 7,6 x 235,3 cm) x72 3" (7,6 cm) x4 7/16 x 2-1/2 x 24-3/4" (1,1 x 6,4 x 62,9 cm) x2 NK 2 x 3 x 48" (5 x 7,6 x 122 cm)

BEGIN


Orient parts on edge on floor. Measure and mark from end of boards.

IMPORTANT! You will build two walls the same.

2 Use two 3" nails at each mark.








10' x 16' SIDE WALL FRAME- SOFFIT

PARTS REQUIRED: x443/8 x 5 x 48" (0,9 x 12,7 x 122 cm) **x2**3/8 x 5 x 93-1/4" (0,9 x 12,7 x 236,9 cm)

- 3 Place panels onto 2 x 3 with primed side against 2 x 3 as shown (Fig A)
 - / Keep panel flush along entire edge of 2 x 3 top plate (Fig A).
- 4 Attach soffit panels flush to 2 x 3 (**Fig A**) and with 3/8" offset at ends (**Fig. B, C**) using nineteen 1-1/4" screws.


GABLE 10' x 16'






10' x 16' SIDE WALL PANELS

PARTS REQUIRED:





x58







Ensure your wall frame is square by installing one panel and squaring frame.

Place the **48 x 72"** panel onto wall frame with primed side up as shown. Note the lip and square edges.


Use the gauge block to mark the 3/4" measurement on the wall stud. Locate the panel flush under the soffit panel. Secure panel with two 2" nails in the corners (Fig. A).



Move to the opposite end. Using the long edge of the panel as a lever move the panel side-to-side until you have a 3/4" measurement on the wall stud. Secure corner with two 2" nails.



37



10' x 16' SIDE WALL PANELS **PARTS REQUIRED:** x238 2" (5 cm) 3/8" x 48" x 72" **x6** (1 x 122 x 183 cm) Place 48" panels on frame as shown with primed side facing up. NOTE THE SQUARE AND LIP EDGES. Do not nail in groove. Nail using 2" nails 6" apart on edges and 12" apart inside panel. To draw panels tight at seams angle nail. Flush 12" (30 cm) 6" (15 cm) 48" 48" 48" (122 cm) (122 cm) (122 cm) Carefully flip your sidewall over. Repeat STEPS 1-8 to assemble your second side wall. FINISH


10 You have finished building both of your side walls. Go to page 39.

BACK WALL INSTALLATION

PARTS REQUIRED (TEMPORARY):

00

2 x 3 x 69" (5 x 7,6 x 175,3 cm)




Do not nail in groove.




BEGIN

- 1 Center back wall assembly on the 120" (305 cm) floor dimension.
- Use **00** as a temporary brace. Secure with two 3" screws.








- First, nail lower edge of panel to floor frame using 2" nails 6" apart Angle nail to hit floor frame (Fig. A).
- Screw back wall uprights to floor using two 3" screws (Fig. B).



You have finished standing your back wall. /Nail 2" nails first. Angle to nail into floor frame. NOTE: 10'x8' Gable Shown. 2" (5 cm) Nail Fig. A 00 3" (7,6 cm) Screw 6" (15 cm) Fig. B (7,6 cm) Screw (7,6 cm) Screw (7,6 cm) (5 cm) Nail Screw





3" (7,6 cm) Nail

(7,6 cm) Screw

Fig. F

FRONT WALL INSTALLATION





Fig. E

Fig. G


2 x 3 x 54-5/16" (5 x 7,6 x 138 cm)

NOTE: 10'x8' Gable Shown





- Position one CD flush to front panel edge and center on right edge of groove (Fig. A). Attach trim with eight 1-1/4" screws from inside. Install two screws at seam (Fig. B).





Repeat steps 1-2 to attach the back trim.



You have attached your upper trim. Continue to attaching your endcaps. ≥Flush Fig. B Fig. A CD Flush to top of panel. (20,3 cm

3/4 x 3-1/2 x 5" (1,9 x 9 x 12,7 cm)

x4

3/4 x 3-1/2 x 8-1/2" (1,9 x 9 x 21,6 cm)


x4 $3/4 \times 6-1/4 \times 11-7/8$ " (1,9 x 15,8 x 30 cm) **LEFT PAINTED GREEN**


RIGHT PAINTED RED



BEGIN

- Glue 5" and 8-1/2" boards onto endcaps, and fasten with 1-1/4" screws, as shown.
- Repeat steps to build two more endcaps.
- Locate endcaps flush with upper trim and corner trim and attach each endcap from inside of shed using four 1-1/4" screws as shown (Fig. A).
- FINISH You have attached your endcaps.







GABLE 10' x 8'


GABLE 10' x 12'

Align over studs.

Maintain the measurements between rafters.







BEGIN

Locate rafters directly over studs and flush to overhang in wall frame (Fig. A). Check that you have the measurements shown. Screw through soffit panel into rafters using one 2" screw (Fig. A).





Repeat steps to attach (5) rafters.



GABLE 10' x 12


FINISH You have attached your rafters. Go to page 48.






Maintain the measurements between rafters.

RAFTER INSTALL 10' x 16' **x28 PARTS REQUIRED:** 3" (7,6 cm) **x14** pre-assembled **x7 √**BEGIN Locate rafters directly over studs and flush to overhang in wall frame (Fig. A). Check that you have the measurements shown. Screw through soffit panel into rafters using one 2" screw (Fig. A). Attach with two 3" screws at each end (Fig. B). Re-tighten 2" screws if neccessary. Repeat steps to attach (5) rafters. FINISH You have attached your rafters. Go to page 49. Fig. B





Maintain the measurements between rafters.

TRIM 10' x 8"

PARTS REQUIRED:

1 x 3 x 94-3/4" (2,5 x 7,6 x 240,6 cm)






- FOR 10' x 12', SKIP TO PAGE 48.
- FOR 10' x 16', SKIP TO PAGE 49.



- Attach fascia trim flush to bottom of soffit (Fig. A) and endcaps at ends of rafters (Fig. B) using 2" (5 cm) nails as shown.
- 2 Repeat steps to attach fascia trim on both sides.



3 You have attached your fascia trim. Go to page 50.



TRIM 10' x 12'


PARTS REQUIRED:

x2 HS

1 x 3 x 94-3/4" (2,5 x 7,6 x 240,6 cm)

FO **x2**

1 x 3 x 48" (2,5 x 7,6 x 122 cm)



BEGIN


Attach fascia trim flush to bottom of soffit (Fig. A) and endcaps (Fig. B) using 2" (5 cm) nails as shown. Nail trim to end of rafters and toe-nail trim together (Fig. C) using (1) 2" (5 cm) nail as shown.



Repeat steps to attach fascia trim on both sides.

FINISH

You have attached your fascia trim. Go to page 52.



TRIM 10' x 16'


PARTS REQUIRED:

x2 HS

1 x 3 x 94-3/4" (2,5 x 7,6 x 240,6 cm)

x4 FO

1 x 3 x 48" (2,5 x 7,6 x 122 cm)



BEGIN


Attach fascia trim flush to bottom of soffit (Fig. A) and endcaps (Fig. B) using 2" (5 cm) nails as shown. Nail trim to end of rafters and toe-nail trim together (Fig. C) using (1) 2" (5 cm) nail as shown.



2 Repeat steps to attach fascia trim on both sides.



3 You have attached your fascia trim. Go to page 54.




ROOF PANELS 10' x 8'

PARTS REQUIRED:

x2

7/16 x 48 x 96" (1,1 x 122 x 244 cm)





- FOR 10' x 12', SKIP TO PAGE 52.
- FOR 10' x 16', SKIP TO PAGE 54.

<u>(1</u>)

Roof panels may cause serious injury until securely fastened.



Sec. 1


You must square the roof by attaching one panel first. You will use the panel's long edge as a lever to bring your roof into square. Commonly known as "racking".

VBEGIN




Attach the **48 x 96"** panel with the rough side up (painted-grid lines side) with a 1/8" measurement on the rafter (**Fig A**) and the panel flush at the peak (**Fig. B**).

Secure panel with two 2" nails in the corners.



Move to the opposite end. Using the long edge of the panel as a lever move the panel side-to-side until the top corner is flush to the peak (Fig. C) and there is a 1/8" (0,3 cm) measurement to the gable trim (Fig. D).

You may need to move your backwall to get the 1/8" measurement. Secure panel with two 2" nails in the corners.




ROOF PANELS 10' x 8'

PARTS REQUIRED:

x2

7/16 x 19 x 96" (1,1 x 48 x 244 cm)



Keep spacing between the center of the rafters at the lower edge of the panel and secure with one 2" nail into each rafter (Fig. E).

> Move to the top of the panel and keep spacing between the center of the rafters. Secure with one 2" nail into each rafter (Fig. E).

Nail the roof panel using 2" nails 6" apart on edges and 12" apart inside panel (Fig. F).





Fig. E

Attach the lower roof panels flush to the upper panels and with a 1/8" (0,3 cm) measurement at the gable trim (Fig.G).

> Nail the roof panel using 2" nails 6" apart on edges and 12" apart inside panel.


Repeat process to attach roof panels on the opposite side.

FINISH You have attached your roof panels.



Go to page 56.





ROOF PANELS 10' x 12'

PARTS REQUIRED: x 4 2" (5 cm) 7/16 x 48 x 96" **x2** (1,1 x 122 x 244 cm) **GAUGE BLOCK**

Roof panels may cause serious injury until securely fastened.

You must square the roof by attaching one panel first. You will use the panels' long edge as a lever to bring your roof into square. Commonly known as "racking".




Flush at peak.

VBEGIN


Attach the 48 x 96" panel with the rough side up (painted-grid lines side) with a 3/4" (1,9 cm) measurement on the rafter (Fig A) and the panel flush at the peak (Fig. B).

Secure panel with two 2" nails in the corners.



Move to the opposite end. Using the long edge of the panel as a lever move the panel side-to-side until the top corner is flush to the peak (Fig. C) and there is a 1/8" (0,3 cm) measurement to the gable trim (Fig. D).

> You may need to move your backwall to get the 1/8" measurement. Secure panel with two 2" nails in the corners.



ROOF PANELS 10' x 12' PARTS REQUIRED: x2 47-7/8" x 48" (121,6 x 122 cm) 7/16 x 19 x 96" (1,1 x 48 x 244 cm) x2 19" x 48" (48 x 122 cm)

3 Keep spacing between the center of the rafters at the lower edge of the panel and secure with one 2" nail into each rafter (Fig. E).

Move to the top of the panel and keep spacing between the center of the rafters. Secure with one 2" nail into each rafter (Fig. E).

Nail the roof panel using 2" nails 6" apart on edges and 12" apart inside panel (Fig. F).

Attach 47-7/8" x 48" roof panel flush to the peak. (Fig.G) and with a 1/8" (0,3 cm) measurement at the gable trim (Fig. H).

Attach lower 19" x 48" roof panel flush to the top panel and with a 1/8" (0,3 cm) measurement at the gable trim (Fig. I).


Attach next lower 19"x96" roof panel flush to top panel


Nail the roof panels using 2" nails 6" apart on edges and 12" apart inside panel.


Repeat process to attach roof panels on the opposite side.

Go to page 56.









ROOF PANELS 10' x 16'

PARTS REQUIRED: x2 7/16 × 48 × 96" (1,1 × 122 × 244 cm) GAA 3/4" GAUGE BLOCK

<u>(1</u>)

Roof panels may cause serious injury until securely fastened.


You must square the roof by attaching one panel first. You will use the panels' long edge as a lever to bring your roof into square. Commonly known as "racking".



BEGIN

Attach the **48 x 96"** panel with the rough side up (painted-grid lines side) with a 3/4" (1,9 cm) measurement on the rafter (**Fig A**) and the panel flush at the peak (**Fig. B**).


Secure panel with two 2" nails in the corners.



Flush at peak.


Move to the opposite end. Using the long edge of the panel as a lever move the panel side-to-side until the top corner is flush to the peak (Fig. C) and there is a 3/4" (1,9 cm) measurement on the rafter (Fig. D).


You may need to move your rafter to get the 3/4" measurement. Secure panel with two 2" nails in the corners.











x2

7/16 x 19 x 96" (1,1 x 48 x 244 cm)

x4



19" x 48" (48 x 122 cm)

Keep spacing between the center of the rafters at the lower edge of the panel and secure with one 2" nail into each rafter (Fig. E).

Move to the top of the panel and keep spacing between the center of the rafters. Secure with one 2" nail into each rafter (Fig. E).

Nail the roof panel using 2" nails 6" apart on edges and 12" apart inside panel (Fig. F).

Attach 47-7/8" x 48" roof panels flush to the peak. (Fig.G) and with a 1/8" (0,3 cm) measurement at the gable trim (Fig. H, I).





Fig. E 1/8" (0,3 cm) Fig. H 12" / (30,5 cm)

Attach the lower 19"x96" roof panel flush to top panel

> Attach the lower 19"x48" roof panels flush to the top panels and with a 1/8" (0,3 cm) measurement at the gable trim (Fig. J).

Nail the roof panels using 2" nails 6" apart on edges and 12" apart inside panel.


Repeat process to attach roof panels on the opposite side.




(0,3 cm)

Fig. F







10' x


GABLE

×


GABLE 10'

GABLE 10' x 16'

Attach temporary support **GAA** at bottom with 1-1/4" screws (**Fig. A**). Tighten securely.





DOORS PARTS REQUIRED: x1 OO 2 x 3 x 69" (5 x 7,6 x 175,3 cm)



- 4 Center doors on right edge of groove as shown (Fig. B).
 - ! Check ledger board is still flush under panels.
- Screw hinge boards into wall supports and floor using four 3" screws as shown.

 New York Make sure screws go into framing and floor (Fig. C, D).
- Remove temporary supports and check doors open properly.






DOOR WEATHERSTRIP

PARTS REQUIRED:

00

2 x 3 x 69" (5 x 7,6 x 175 cm)




BEGIN

- With left door closed, center a weatherstrip **00** vertically on the left door in the door opening (Fig. A). OO will offset the left door 1" OUT past the door trim 1" (Fig. B).
- Secure **00** using seven 3" screws through outside trim into **00** (Fig. B)
- On right door center **OO** vertically in door opening (Fig. A). **OO** will offset the right door 1" IN from the door trim (Fig. C).
- Secure **OO** using seven 3" screws through outside trim into **OO** (**Fig. C**).



You have finished installing your door weatherstrips.





<u></u>


GABLE 10' X

DOOR HARDWARE

PARTS REQUIRED:













- Mount barrel bolt flush at top of **OO** on left door using 3/4" screws as shown (Fig A).
- With door closed mark hole location for bolt to extend into. HINT: Extend bolt to leave a mark in wood. Tap bolt with hammer. Drill 3/8" hole deep enough for bolt to slide into.
- Install hasp on right door and latch on left door. Bottom edge of hasp is





PAINT & CAULK - NOT INCLUDED -




- Use acrylic latex caulk that is paintable. Caulk at all horizontal and vertical seams, between the trim and walls, and all
 around the door trim.
- Use a high quality exterior acrylic latex paint. When painting your building, there are a few key areas that can be easily overlooked that must be painted:
 - Bottom edge of all siding and trim
 - Inside of doors and all 4 edges

Note:

Prime all un-primed exterior wood before painting. (Follow directions provided by manufacturer.)

ROOF FELT - NOT INCLUDED -

• Install felt flush to all roof edges overlapping 3". Use minimal amount of roofing nails to hold in place.




DRIP EDGE- NOT INCLUDED -



bend over to other side of roof.

(Follow directions provided by manufacturer.)

NOTE: 10'x8' Model Shown



61


SHINGLES - NOT INCLUDED -

· Follow directions provided by manufacturer and these instructions.





Familiarize yourself with a 3-Tab Shingle.



!\ NEVER DRIVE FASTENERS INTO OR ABOVE SEALING STRIPS.


VBEGIN

1

Install first starter row upside down and color up with a 1" overhang at back and bottom of roof panel. Use (4) nails per shingle.


Starter row must be straight and level all the way across with lower edge of roof deck.

NOTE: If you have installed drip edge install shingles flush to drip edge.





SHINGLES continued...

2 Beginning at front of shed, install first row of shingles with notch at 1" past roof edge or flush with drip edge.




Install second row of shingles flush at top of first row's rain slots. Ensure 1" overhang or flush to drip edge at front, stagger each row.






SHINGLES continued...

Continue installing rows of shingles to the peak. At the peak make sure there is a maximum of 5" or less to the rain slot, as shown below. If shingles overlap at ridge cut to peak with a utility knife.



- / !\ · If more than 5" to rain slot you must install another row of shingles.

- Repeat steps 1 5 to shingle the opposite side of your roof. Trim shingles at ridge.
- Once both sides are shingled you need to trim ends. Strike a chalk line 1" from edge.
- Using your shingle hooked blade carefully cut shingles along chalk line.






You have finished shingling your roof. Proceed to capping the ridge.


SHINGLES - RIDGE CAP

• You will finish off the top of the roof with a ridge cap made from shingles.




BEGIN


Cut shingles into THREE pieces. Hint: Use cut-off pieces first.



2 Install first ridge cap flush to shingles at front, as shown.




3 Install second ridge cap 5" back, as shown.




SHINGLES - RIDGE CAP

continued...


4 Continue installing ridge cap to back of roof.




Make sure there is 4" between the shingle-color and edge of shingles.



6 When you have 4" minimum of shingle color cut one piece to cap your roof.



7 Install flush to shingles.



FINISH

You have finished your ridge cap.

WARRANTY

Backyard Storage Solutions, LLC warrants the following:

- Every product is warranted from defects in workmanship and manufacturing for one year.
- 2. All hardware and metal components are warranted for two years.
- 3. Trim is warranted for 10 years.
- 4. Waferboard siding and sheathing is warranted for two years.
- SmartSide[™] siding is warranted for 10 years on all Marco series buildings and 15 years on all Premier Series buildings.
- 6. Timber series buildings' siding and trim are warranted for 10 years.
- 7. Solar Shed windows are warranted for 1 year.
- 8. Cedar lumber is warranted for 15 years.
- 9. Cedar doors and Cedar Garden Center are warranted for 10 years.
- Metal roof is warranted for 25 years.

Backyard Storage Solutions, LLC will repair, replace or pay for the affected part. In no event shall Backyard Storage Solutions, LLC pay the cost of labor or installation or any other costs related thereto. All warranties are from date of purchase. If a cash refund is paid on an affected part, it will be prorated from the date of purchase.

CONDITIONS

The warranty is effective only when:

- 1. The unit has been erected in accordance with the assembly instructions.
- The unit has been properly shingled and painted or stained and reasonably and regularly maintained thereafter.
- 3. The failure occurs when the unit is owned by the original purchaser.
- 4. Backyard Storage Solutions, LLC has received the warranty registration card within thirty (30) days of purchase and notification of the failure in writing within the warranty period specified above.
- 5. Backyard Storage Solutions, LLC has had reasonable opportunity during the sixty (60) days following receipt of notification to inspect and verify the failure prior to commencement of any repair work.

REQUIREMENTS

Storage Buildings & Playhouses

To validate your warranty, it is necessary to properly maintain your Backyard Storage Solutions, LLC unit; shingle the roof and paint or solid-colored stain the siding using 100% acrylic latex exterior product with a minimum of two (2) coats within thirty (30) days of assembly; caulk above all doors and all horizontal and vertical trim boards; paint and seal all exposed edges, sides and faces of SmartSide™ and waferboard siding to include all exterior walls and all sides and all edges of doors.

Gazebos, Pergolas & Timber Buildings

To validate your warranty, it is necessary to properly maintain your Backyard Storage Solutions, LLC unit. This includes treating all of the exposed cedar and pine surfaces on your gazebo or timber building with an exterior grade wood preservative, an exterior oil-based semi-transparent stain, an acrylic latex exterior paint or an acrylic latex solid color exterior stain within 30 days of assembly and as needed thereafter to maintain your warranty.

Keep vegetation trimmed away from building and make sure siding panels and trim do not come in contact with masonry or cement. The minimum ground clearance for siding must be one half inch (½ inch) from concrete slab or two and one half inches (2 ½") from the ground when building is erected or constructed on a treated wood floor kit. Water from sprinklers must be kept off unit. In no event will Backyard Storage Solutions, LLC be responsible for any indirect, incidental, consequential or special damages nor for failure(s) that are caused by events, acts or omissions beyond our control including, but not limited to, misuse or improper assembly, improper maintenance (which eventually leads to rot or decay) and acts of God. Backyard Storage Solutions, LLC will not be held responsible for any labor costs incurred to construct your unit. This warranty gives you certain specific rights that vary from state to state.

CLAIM PROCEDURE

To make a claim under this warranty, you can either call 1-888-827-9056 or prepare a letter. Please have ready the information below when you call or include the information when writing:

- 1. The model and size of the product.
- 2. A list of the part(s) for which the claim is made.
- 3. Proof of purchase of the Backyard Storage Solutions, LLC item, as shown on the original invoice.
- 4. Run code, as listed on the yellow warranty card enclosed in the product package.

Mail the above information to:

Backyard Storage Solutions, LLC Attn: Customer Service 1000 Ternes Monroe, MI 48162

*WARRANTY TERMS MAY VARY OUTSIDE THE U.S.A.

IMPORTANT: This is your warranty certificate.

Please complete and mail your warranty card to properly validate your warranty.

67

Limited Conditional Warranty *