



1 1/2" PIPE



Insert into pipe. Rotate nut clockwise until PlugAll does not easily slip inside pipe. Rotate nut a maximum of 2 full turns. Then, check for leaks.

2" PIPE
1 1/2" &
2" CLEANOUT



Insert into pipe. Rotate nut clockwise until it has become hand tight. Then, check for leaks.

WARNING: Hand tighten only. Do not overtighten.

CAUTION: Stand clear when pressure testing.

AVERTISSEMENT : Serrez à la main uniquement. Ne serrez pas trop.

ATTENTION : Écartez-vous pendant les tests de pression.